



## 18th & 19th Century American Oak

Pattern	Construction	Profile	Edge	Finish	Installation
Mixed Planks	Engineered	Tongue and Groove	N/A	Unfinished & Sanded	Glue

### Engineered

<b>Overall Thickness</b>	15(4)mm / 9/16"
<b>Width</b>	mixed widths 55/90/120mm / 2 3/16", 3 9/16", 4 3/4"
<b>Length</b>	400-2000mm / 15 3/4" - 78 3/4"
<b>Underfloor Heating</b>	By request only


### Tests

<b>Janka</b>	1120
<b>Moisture</b>	8-12%

## Grading

<b>Species</b>	American Oak (Quercus Robur)
<b>Grade</b>	Reclaimed
<b>Maximum Open Filled Knots</b>	Unfilled, Open Holes
<b>Maximum Size of Closed Knots</b>	Unfilled, Open Holes
<b>End Checks</b>	No longer than width of board allowed (max. 2mm open)
<b>Filler</b>	Unfilled, Open Holes
<b>Filled Crack</b>	NA

## Tonal Variation




This product will exhibit natural colour variation because of the in depth colouring process. You can expect to see **tonal variation between -1 and +1** due to natural oxidation and reaction to the atmosphere, this product will tonally settle.

## Sustainability & Certifications

FSC, PEFC	Tree Planting	EUTR	LACEY ACT	Formaldehyde Emission
NA	Yes	NA	Yes	E1 (0.1ppm): complete compliance with EU safety standards



# Mouldings





N.B. For a seamless transition, we can colour-match the selected moulding with this product.

## Staircase

We offer the opportunity to customise stairs to complement or match our wood flooring.

1. Stairs and claddings are available in a variety of construction types and styles.
2. Stair material is available to match the majority of our wood floors.
3. We offer both contemporary and traditional nosing styles.
4. Stairs are either constructed using our finest engineered platforms or solid wood. Construction will vary depending on nosing types.



## Guarantees

### Lifetime Structural Guarantee:

The Company's warranty commitment is to provide the retail purchaser quality wood flooring that is free from structural defects in milling for the lifetime of the product, where products have been installed to our guidelines and the site conditions for temperature and humidity are met).